

TABLE R303.2.1
ROOF SHEATHING ATTACHMENTS, b

Rafter/Truss Spacing 24 in. o.c.	WIND SPEED																							
	115 mph			120 mph			130 mph			140 mph			150 mph			160 mph			170 mph			180 mph		
	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F
Rafter/Truss SG = 0.42	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Rafter/Truss SG = 0.41	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6






TABLE R303.2.2
MINIMUM ROOF SHEATHING THICKNESS

Rafter/Truss Spacing 24 in. o.c.	WIND SPEED																							
	115 mph			120 mph			130 mph			140 mph			150 mph			160 mph			170 mph			180 mph		
Rafter/Truss SG = 0.42	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)	7/16	(24/16)

R303.2.2 Allowable spans
The minimum thickness and span rating for wood structural panel roof sheathing shall not exceed the values set forth in Table R303.2.2

TABLE R303.2.2
MINIMUM ROOF SHEATHING THICKNESS

Rafter/Truss Spacing 24 in. o.c.	WIND SPEED																							
	115 mph			120 mph			130 mph			140 mph			150 mph			160 mph			170 mph			180 mph		
Rafter/Truss SG = 0.42	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6



DESIGN PARAMETERS:

APPLICABLE CODES:
BUILDING CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023
MECHANICAL CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, MECHANICAL 2023
PLUMBING CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, PLUMBING 2023

ELECTRICAL CODE = NEC 2020
FLORIDA FIRE PREVENTION CODE = 8TH EDITION
LIFE SAFETY CODE = NFPA 101 8TH EDITION

ACCESSIBILITY CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023
ENERGY CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023

METHOD OF DESIGN:
DESIGNED PURSUANT TO (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023, CHAPTER 3 AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE

BASIC WIND SPEED:
 115 MPH (ULTIMATE DESIGN) = 132.0 MPH (NOMINAL DESIGN)
 120 MPH (ULTIMATE DESIGN) = 124 MPH (NOMINAL DESIGN)
 130 MPH (ULTIMATE DESIGN) = 116 MPH (NOMINAL DESIGN)

IMPORTANCE FACTOR/COMPONENTS AND CLADDING:
 0.11 (RISK CATEGORY I)
 1.00 (RISK CATEGORY II)
 1.15 (RISK CATEGORY III)
 1.15 (RISK CATEGORY IV)

BUILDING OCCUPANCY CLASSIFICATION:
 GROUP A - ASSEMBLY
 GROUP B - BUSINESS
 GROUP D - DAY CARE CENTER
 GROUP E - EDUCATIONAL
 GROUP F - FACTORY INDUSTRIAL
 GROUP H - HAZARDOUS
 GROUP I - INSTITUTIONAL
 GROUP M - MERCANTILE
 GROUP R - RESIDENTIAL
 GROUP S - STORAGE

TORNADO BASIC WIND SPEED:
 RISK CATEGORY II = N/A
 110 MPH (NORMAL DESIGN F3-SECOND GUST)
 160 MPH (NORMAL DESIGN F3-SECOND GUST)
 150 MPH (NORMAL DESIGN F3-SECOND GUST)

RAIN FALL INFORMATION:
 N/A SLOPED ROOF GREATER THAN 2/12
 RAINFALL DATA FROM FBC PLUMBING 2023 FIGURE 1106.1 IN/HR.
 ROOF AREA IN SF.

BUILDING CONSTRUCTION TYPE:
 TYPE I
 TYPE II
 TYPE III
 TYPE IV
 TYPE V

EXPOSURE CATEGORY:
 A
 B
 C
 D

WINDBORNE DEBRIS REGION:
 NO
 YES

INTERNAL PRESSURE COEFFICIENTS:
 0.00 (OPEN)
 +0.15, -0.18 (ENCLOSED)
 +0.55, -0.55 (PARTIALLY ENCLOSED)

CLASSIFICATION OF WORK:
 ALTERATION
 LEVEL 1
 LEVEL 2
 LEVEL 3
 NEW CONSTRUCTION
 CHANGE OF OCCUPANCY
 ADDITION / REMODEL
 HISTORIC BUILDING

DESIGN LOAD BEARING VALUE OF SOIL 2000 PSF

GENERAL NOTES

1. CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO START OF CONSTRUCTION. DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.

2. MASONRY CONTRACTOR TO VERIFY ALL MASONRY OPENING DIMENSIONS FOR ALL WINDOWS, SLIDING GLASS DOORS, & ENTRY DOORS AS SHOWN ON THESE PLANS WITH THE DOOR AND WINDOW MANUFACTURER PRIOR TO CONSTRUCTION.

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CHECK THESE PLANS FOR DIMENSIONAL ERRORS AND/OR OMISSIONS PRIOR TO CONSTRUCTION. IF ANY ERRORS OR OMISSIONS EXIST IN THE DRAWINGS OR SPECIFICATIONS, THE CONTRACTOR SHALL NOTIFY HICKS DRAFTING & DESIGN IN WRITING WITHIN 10 DAYS OF RECEIPT OF PLANS AND PRIOR TO ANY CONSTRUCTION. CONTRACTOR ASSUMES ALL THE RESPONSIBILITY FOR THE RESULTS AND ALL THE COSTS OF RECTIFYING THE SAME.

4. HICKS DRAFTING & DESIGN DOES NOT ASSUME ANY RESPONSIBILITY FOR SUPERVISION OF CONSTRUCTION. CONTRACTOR TO ADHERE STRICTLY TO THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, CHAPTER 3, AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE, TOGETHER WITH LOCAL AMENDMENTS, AND ALL OTHER APPLICABLE STATE, COUNTY, AND LOCAL STATUTES, ORDINANCES, REGULATIONS, AND RULES.

NOTE: MASTER PLANS FEMA FLOOD ZONES CONSTRUCTION NEW CONSTRUCTION OF ANY RESIDENTIAL STRUCTURE SHALL HAVE THE LOWEST FLOOR OR CONCRETE SLAB, INCLUDING GARAGE OR BASEMENT AND AIG, PWH AND ALL EQUIPMENT, ELEVATED TO FINISH FLOOR ELEV. OR ABOVE THE BASE FLOOD ELEVATION PLUS 1 FOOT. THIS SHALL APPLY TO HOUSES OR MANUFACTURED HOMES THAT ARE TO BE PLACED OR SUBSTANTIALLY IMPROVED ON SITES IN A NEW MANUFACTURED HOME PARK OR SUBDIVISION LDC CHAPTER 6, ARTICLE IV FLOOD HAZARD REDUCTION.

THIS RESIDENCE MAY NOT BE BUILT WITHIN 60' OF ANOTHER STRUCTURE OR 50' FROM ANY PROPERTY LINE PER SECTION R302.1(1) (INCLUDING OVERHANGS)

BUILDING OVERHANG TO BE 5 FEET FROM PROPERTY LINE UNLESS RATED OR FIRE SPRINKLERED TABLE R302.1(1)

DECK BOARDS & STAIR TREADS REQUIRED TO HAVE LABEL R507

ONE LAYER OF WATER RESISTIVE BARRIER BEHIND EXTERIOR SIDING WALL COVERING R103.2

TWO LAYERS OF WATER RESISTIVE BARRIER BEHIND EXTERIOR WALLS WITH WIRE LATH & CEMENTITIOUS FINISH COVERING R103.1.3

PAN FLASHINGS UNDER WINDOWS AND DOORS ON FRAME CONSTRUCTION. REFER TO NOTES R103.4 ON SHEET 3 OF 6

WINDOWS MUST HAVE COMPLIANT SHGC VALUES. REFER TO EXTERIOR OPENING CHART AND ATTACHED ENERGY CALCULATIONS AND WINDOW AND DOOR SPEC SHEETS FROM MANUFACTURERS.

WATER HEATERS AND STORAGE TANKS SHALL BE EQUIPPED WITH PRESSURE RELEASE AND TEMPERATURE VALVES OR A COMBINATION THEREOF 504 WATER TANK SAFETY DEVICES.

THE MAXIMUM DISTANCE BETWEEN A HOT WATER SUPPLY SOURCE AND ALL FIXTURES SERVED BY THE SUPPLY SOURCE HAS BEEN REDUCED FROM 100 FT TO 50 FT. HOT OR TEMPERED WATER SUPPLY TO FIXTURES

REVISIONS:

02-23-2022	
03-20-2024	

PLAN SCHEDULE

SHEET #	DESCRIPTION
1 OF 6	EXTERIOR ELEVATIONS, ROOF PLAN, SECTIONS
2 OF 6	FOUNDATION PLAN, WALL SECTION, AND SECTIONS
3 OF 6	DIMENSIONAL FLOOR PLAN AND SECTIONS
4 OF 6	NOTED FLOOR PLAN, SCHEDULES, AND SECTIONS
5 OF 6	ELECTRICAL PLAN, ELECTRICAL SCHEDULE AND SECTIONS
6 OF 6	ENGINEERING NOTES AND SECTIONS
1A OF 6	ALTERNATE EXTERIOR ELEVATIONS, ROOF PLAN, SECTIONS
5H-1 OF 5H-2	SHOP DRAWINGS
5H-1 OF 5H-2	SHOP DRAWINGS

SEE "TYPICAL FRAMING DETAIL" ON SHEET 5 OF 6 FOR HOLD DOWNS. (TYPICAL @ 12" OPENINGS)

(2) 2 X 12 SYP WITH 1/2" PLYWOOD GLUED AND NAILLED IN SIMPSON ST6236 W/ (40) 16D NAILS AT EACH END, 3 WALLS STUDS BELOW EACH END

(2) 2 X 12 SYP WITH 1/2" PLYWOOD GLUED & NAILLED AT FRONT PORCH

6 X 6 P.T. POSTS TYPICAL AT FRONT PORCH

2 X 4 SYP WALL STUDS @ 16" O.C. INTERIOR BEARING WALL

(2) 1 3/4 X 11 7/8 MICROLAM W/ SIMPSON ST6236 W/ (40) 16D NAILS AT WALL END, 3 WALLS STUDS BELOW EACH END

36" HIGH DEC VINYL RAILINGS NON GUARDRAIL. OPENING WILL REGIST 4" SPHERE. ATTACH PER MANUFACTURERS SPECIFICATIONS.

TRUSS LIABILITY EXCLUSION NOTE

MASTER PLAN

1 AL QUATTRONE APPROVE OF REPETITIVE USE OF PLANS FOR PERMITTING
FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 10 1/2" CANT

BUILDER: HABITAT FOR HUMANITY
4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING

NEW RESIDENCE FOR: / UNIT- / RANGE-
LOT- / BLOCK- / TOWNSHIP-
SECTION- / STRAP#-
ADDRESS:

DRAWN BY: DAVID HICKS
DATE: 01-08-2021
SCALE: 1/4" = 10"
JOB#: 2024-007










SHEET
1 OF 6

Quattrone & Associates, Inc.
Engineers, Planners, & Development Consultants
4400 Vermont Shorebank Blvd., Fort Myers, FL 33916 (239) 936-9222
Certificate of Accreditation Number 9463
AL-QUATTRONE P.E. # 52141

CONFORMANCE STATEMENT
THESE PLANS HAVE BEEN DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER IN ACCORDANCE WITH THE 8TH EDITION OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE (R1609) OF THE 2023 FLORIDA BUILDING CODE.

HICKS DRAFTING & DESIGN
4216 5TH STREET W
LEHIGH ACRES FL 33971
CELL: (239) 462-2734
E-MAIL: DHICKS922@AOL.COM

03-20-2024 REVISION



GENERAL NOTES

- CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO START OF CONSTRUCTION. DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.
- MASONRY CONTRACTOR TO VERIFY MASONRY OPENING DIMENSIONS FOR ALL WINDOWS, SLIDING GLASS DOORS, & ENTRY DOORS AS SHOWN ON THESE PLANS WITH THE DOOR AND WINDOW MANUFACTURER PRIOR TO CONSTRUCTION.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO CHECK THESE PLANS FOR DIMENSIONAL ERRORS AND/OR OMISSIONS PRIOR TO CONSTRUCTION. IF ANY ERRORS OR OMISSIONS EXIST IN THE DRAWINGS OR SPECIFICATIONS, THE CONTRACTOR SHALL NOTIFY HICKS DRAFTING & DESIGN IN WRITING WITHIN 10 DAYS OF RECEIPT OF PLANS AND PRIOR TO ANY CONSTRUCTION. CONTRACTOR ASSUMES ALL THE RESPONSIBILITY FOR THE RESULTS AND ALL THE COSTS OF RECTIFYING THE SAME.
- HICKS DRAFTING & DESIGN DOES NOT ASSUME ANY RESPONSIBILITY FOR SUPERVISION OF CONSTRUCTION. CONTRACTOR TO ADHERE STRICTLY TO THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, CHAPTER 3, AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE, TOGETHER WITH LOCAL AMENDMENTS, AND ALL OTHER APPLICABLE STATE, COUNTY, AND LOCAL STATUTES, ORDINANCES, REGULATIONS, AND RULES.

NOTE: MASTER PLANS
FEMA FLOOD ZONES CONSTRUCTION
NEW CONSTRUCTION OF ANY RESIDENTIAL STRUCTURE SHALL HAVE THE LOWEST FLOOR OR CONCRETE SLAB, INCLUDING GARAGE OR BASEMENT AND A/C P/NH AND ALL EQUIPMENT, ELEVATED TO FINISH FLOOR ELEV. OR ABOVE THE BASE FLOOD ELEVATION PLUS 1 FOOT. THIS SHALL APPLY TO HOUSES OR MANUFACTURED HOMES THAT ARE TO BE PLACED OR SUBSTANTIALLY IMPROVED ON SITES IN A NEW MANUFACTURED HOME PARK OR SUBDIVISION LDC CHAPTER 6, ARTICLE IV FLOOD HAZARD REDUCTION.

THIS RESIDENCE MAY NOT BE BUILT WITHIN 50' OF ANOTHER STRUCTURE OR 50' FROM ANY PROPERTY LINE PER SECTION R302.1(1) (INCLUDING OVERHANGS).

Quattrone & Associates, Inc.
Engineers, Planners, & Development Consultants
4401 Vermont Shorebank Blvd., Fort Myers, FL 33916 (239) 936-9222 Q&A@cc.com
AL QUATTRONE P.E. # 52141

REVISIONS:

02-23-2022
03-20-2024

HICKS DRAFTING & DESIGN
4216 5TH STREET W
LEHIGH ACRES FL 33971
CELL: (239) 462-2734
E-MAIL: DHICKS@922@AOL.COM

ALLOW FOR ELECTRICAL IN SLAB AS REQ BY OWNER OR BUILDER. ELECTRICAL CONTRACTOR TO VERIFY NEEDS WITH CONTRACTOR PRIOR TO START OF CONSTRUCTION. ALLOW FOR ELECTRICAL IN SLAB IN KITCHEN AREA FOR CABINETS, SINK, D/W, AND ALL OTHER ELEC NEEDS IN ALL 8\"/>

CONTRACTOR IS RESPONSIBLE FOR VERIFYING ROUGH OPENINGS AND SIZES OF ALL DOORS AND WINDOWS BEFORE STARTING CONSTRUCTION. PROVIDE 1\"/>

NOTE: ALL EXTERIOR WALLS ARE 3 1/2\"/>

FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 10 1/2\"/>

BUILDER: HABITAT FOR HUMANITY
4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING

NEW RESIDENCE FOR:
LOT: / BLOCK- / UNIT- / RANGE-
SECTION: / TOWNSHIP- /
STRAP#:
ADDRESS:

DRAWN BY:
DAVID HICKS

DATE: 01-08-2021

SCALE: 1/4"=10"


JOB#: 2024-007

SHEET
2 OF 6 SHEET


R703.4 Flashing.

Approved metal flashing, vinyl flashing, self-adhered membranes and mechanically attached flexible flashing shall be applied shingle-fashion or in accordance with the manufacturer's instructions. Metal flashing shall be corrosion resistant. Fluid-applied membranes used as flashing shall be applied in accordance with the manufacturer's instructions. All flashing shall be applied in a manner to prevent the entry of water into the wall cavity or penetration of water to the building structural framing components. Self-adhered membranes used as flashing shall comply with AAMA T11. All exterior fenestration products shall be sealed at the juncture with the building wall with a sealant complying with AAMA 800 or ASTM C920 Class 25 Grade NS or greater for proper joint expansion and contraction, ASTM C1201, AAMA 812, or other approved standard as appropriate for the type of sealant. Fluid-applied membranes used as flashing in exterior walls shall comply with AAMA T14. The flashing shall extend to the surface of the exterior wall finish. Approved flashings shall be installed at the following locations:




1. Exterior window and door openings. Flashing at exterior window and door openings shall extend to the surface of the exterior wall finish or to the water-resistive barrier complying with Section 703.2 for subsequent drainage. Mechanically attached flexible flashings shall comply with AAMA T12. Flashing at exterior window and door openings shall be installed in accordance with one or more of the following:
 - 1.1. The fenestration manufacturer's installation and flashing instructions, or for applications not addressed in the fenestration manufacturer's instructions, in accordance with the flashing or water-resistive barrier manufacturer's instructions. Where flashing instructions or details are not provided, pan flashing shall be installed at the sill of exterior window and door openings. Pan flashing shall be sealed or sloped in such a manner as to direct water to the surface of the exterior wall finish or to the water-resistive barrier for subsequent drainage. Openings using pan flashing shall incorporate flashing or protection at the head and sills.
 - 1.2. In accordance with the flashing design or method of a registered design professional.
 - 1.3. In accordance with other approved methods.
 - 1.4. In accordance with FMA/AAMA 100, FMA/AAMA 200, FMA/NDMA 250, FMA/AAMA/NDMA 300 or FMA/AAMA/NDMA 400, or FMA/AAMA/NDMA 2110.
2. At the intersection of chimneys or other masonry construction with frame or stucco walls, with projecting lips on both sides under stucco copings.
3. Under and at the ends of masonry wood or metal copings and sills.
4. Continuously above all projecting wood trim.
5. Where exterior porches, decks or stairs attach to a wall or floor assembly of wood-frame construction.
6. At wall and roof intersections.
7. At built-in gutters.



PAN FLASHING UNDER WINDOWS AND DOORS ON FRAME CONSTRUCTION NEED TO COMPLY WITH AAMA711 IF SELF-ADHERED MEMBRANES ARE USED AS FLASHING R703.4



DIMENSIONAL FLOOR PLAN



DETAIL

SCALE: 1 1/2" = 1'0"

- GENERAL NOTES**
1. CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO START OF CONSTRUCTION. DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.
 2. MASONRY CONTRACTOR TO VERIFY MASONRY OPENING DIMENSIONS FOR ALL WINDOWS, SLIDING GLASS DOORS, & ENTRY DOORS AS SHOWN ON THESE PLANS WITH THE DOOR AND WINDOW MANUFACTURER PRIOR TO CONSTRUCTION.
 3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CHECK THESE PLANS FOR DIMENSIONAL ERRORS AND/OR OMISSIONS PRIOR TO CONSTRUCTION. IF ANY ERRORS OR OMISSIONS EXIST IN THE DRAWINGS OR SPECIFICATIONS, THE CONTRACTOR SHALL NOTIFY HICKS DRAFTING & DESIGN IN WRITING WITHIN 10 DAYS OF RECEIPT OF PLANS AND PRIOR TO ANY CONSTRUCTION. CONTRACTOR ASSUMES ALL THE RESPONSIBILITY FOR THE RESULTS AND ALL THE COSTS OF RECTIFYING THE SAME.
 4. HICKS DRAFTING & DESIGN DOES NOT ASSUME ANY RESPONSIBILITY FOR SUPERVISION OF CONSTRUCTION. CONTRACTOR TO ADHERE STRICTLY TO THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, CHAPTER 3, AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE, TOGETHER WITH LOCAL AMENDMENTS, AND ALL OTHER APPLICABLE STATE, COUNTY, AND LOCAL STATUTES, ORDINANCES, REGULATIONS, AND RULES.

NOTE: MASTER PLANS FOR FLOOD ZONES CONSTRUCTION NEW CONSTRUCTION OF ANY RESIDENTIAL STRUCTURE SHALL HAVE THE LOWEST FLOOR OR CONCRETE SLAB, INCLUDING GARAGE OR BASEMENT AND AIG P/NH AND ALL EQUIPMENT, ELEVATED TO FINISH FLOOR ELEV. OR ABOVE THE BASE FLOOD ELEVATION PLUS 1 FOOT. THIS SHALL APPLY TO HOUSES OR MANUFACTURED HOMES THAT ARE TO BE PLACED OR SUBSTANTIALLY IMPROVED ON SITES IN A NEW MANUFACTURED HOME PARK OR SUBDIVISION LDCD CHAPTER 6, ARTICLE IV FLOOD HAZARD REDUCTION.

THIS RESIDENCE MAY NOT BE BUILT WITHIN 50' OF ANOTHER STRUCTURE OR 50' FROM ANY PROPERTY LINE PER SECTION R302.1(1) (INCLUDING OVERHANGS)

Quattrone & Associates, Inc.
Engineers, Planners, & Development Consultants
4400 Vermont Shorebank Blvd., Fort Myers, FL 33916 (239) 936-9222 QAM@ca.com
AL: QUATRONE P.E. # 52141

REVISIONS:

02-23-2022
03-20-2024

COMPLIANCE STATEMENT: THESE PLANS HAVE BEEN DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER IN ACCORDANCE WITH THE 2023 FLORIDA RESIDENTIAL BUILDING CODE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE.

HICKS DRAFTING & DESIGN
4216 5TH STREET W
LEHIGH ACRES FL 33971
CELL: (239) 462-2734
E-MAIL: DHICKS@922@AOL.COM

FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 110 1/2" CANT

BUILDER: HABITAT FOR HUMANITY
4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING

NEW RESIDENCE FOR:
LOT: / BLOCK- / UNIT- / RANGE-
SECTION: / TOWNSHIP- / ADDRESS:
STRAP#

DRAWN BY:
DAVID HICKS

DATE: 01-08-2021

SCALE: 1/4" = 1'0"


JOB#: 2024-007

SHEET
3 OF 6

03-20-2024 REVISION


03-20-2024

NOTE: THIS SECTION SHOWS FOR THE EXTERIOR SHEATHING TO EXTEND TO THE TOP OF UPPER 2 X OF THE DOUBLE TOP PLATE OF THE WALLS HOWEVER IT IS ACCEPTABLE THAT THE EXTERIOR SHEATHING IS NAILED TO THE BOTTOM PLATE OF THE DOUBLE TOP PLATE. USE SINGLE ROW OF 8D RINGSHANK NAILS @ 4" O.C. AT EDGES AND 6" O.C. AT INTERIOR LOCATIONS. THE BOTTOM PLATE IS TO BE TIED TO THE TOP PLATE AND THE ROOF TRUSS WITH SIMPSON H-10A CONNECTOR DOUBLE TOP PLATE ATTACHED TO WALL STUD WITH H-2.5A CLIP AS SHOWN ON WALL FRAMING SECTION SHEET 5 OF 6.




EXTERIOR WALL NAILING DETAIL

SCALE: N.T.S.



Simpson Strong-Tie
H10A
HURRICANE CLIP
@ EXT. BEARING WALL

1
4



Simpson Strong-Tie
H10A
HURRICANE CLIP @
EXT. BEARING WD. BEAM

2
4

- GENERAL NOTES
- CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO START OF CONSTRUCTION. DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.
 - MASONRY CONTRACTOR TO VERIFY MASONRY OPENING DIMENSIONS FOR ALL WINDOWS, SLIDING GLASS DOORS, & ENTRY DOORS AS SHOWN ON THESE PLANS WITH THE DOOR AND WINDOW MANUFACTURER PRIOR TO CONSTRUCTION.
 - IT IS THE CONTRACTOR'S RESPONSIBILITY TO CHECK THESE PLANS FOR DIMENSIONAL ERRORS AND/OR OMISSIONS PRIOR TO CONSTRUCTION. IF ANY ERRORS OR OMISSIONS EXIST IN THE DRAWINGS OR SPECIFICATIONS, THE CONTRACTOR SHALL NOTIFY HICKS DRAFTING & DESIGN IN WRITING WITHIN 10 DAYS OF RECEIPT OF PLANS AND PRIOR TO ANY CONSTRUCTION. CONTRACTOR ASSUMES ALL THE RESPONSIBILITY FOR THE RESULTS AND ALL THE COSTS OF RECTIFYING THE SAME.
 - HICKS DRAFTING & DESIGN DOES NOT ASSUME ANY RESPONSIBILITY FOR SUPERVISION OF CONSTRUCTION. CONTRACTOR TO ADHERE STRICTLY TO THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, CHAPTER 3, AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE, TOGETHER WITH LOCAL AMENDMENTS, AND ALL OTHER APPLICABLE STATE, COUNTY, AND LOCAL STATUTES, ORDINANCES, REGULATIONS, AND RULES.

NOTE: MASTER PLANS FEMA FLOOD ZONES CONSTRUCTION NEW CONSTRUCTION OF ANY RESIDENTIAL STRUCTURE SHALL HAVE THE LOWEST FLOOR OR CONCRETE SLAB, INCLUDING GARAGE OR BASEMENT AND A/C UNIT AND ALL EQUIPMENT, ELEVATED TO FINISH FLOOR ELEV. OR ABOVE THE BASE FLOOD ELEVATION PLUS 1 FOOT. THIS SHALL APPLY TO HOUSES OR MANUFACTURED HOMES THAT ARE TO BE PLACED OR SUBSTANTIALLY IMPROVED ON SITES IN A NEW MANUFACTURED HOME PARK OR SUBDIVISION LCD CHAPTER 6, ARTICLE IV FLOOD HAZARD REDUCTION.

THIS RESIDENCE MAY NOT BE BUILT WITHIN 60' OF ANOTHER STRUCTURE OR 50' FROM ANY PROPERTY LINE PER SECTION R302.1(1) (INCLUDING OVERHANGS)

Quattrone & Associates, Inc.
Engineers, Planners, & Development Consultants
4400 Vermont Shorebank Blvd., Fort Myers, FL 33916 (239) 936-6322 Q&A.com
AL QUATTRONE P.E. # 52141
Certificate of Authorization Number 9463

CONFORMANCE STATEMENT
THESE PLANS HAVE BEEN DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER IN COMPLIANCE WITH THE 2023 FLORIDA RESIDENTIAL BUILDING CODE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE.

REVISIONS:
02-23-2022
03-20-2024

DOOR LEGEND			
FEET	WIDTH		HEIGHT
	INCHES	INCHES	
3	0	6	8
			PKT

PKT= POCKET
BF= BI-FOLD
BP= BI-PASS
FR= FRENCH
FX= FIXED
MIR= MIRROR
O.H.G.D.= OVER HEAD GARAGE DOOR
S.G.D.= SLIDING GLASS DOOR
S.C.= SOLID CORE

NOTE: ALL NAILING @ ALL SURFACES TO BE NAILED W/ 8D RING SHANK NAILS

AREA SCHEDULE	
LIVING A/C	1416 SQ. FT.
GARAGE	294 SQ. FT.
FRONT PORCH	62 SQ. FT.
TOTAL	1772 SQ. FT.

*NOTE:
BOTTOM CHORD OF ALL TRUSSES IN LANAI AND ENTRY (AREAS EXPOSED TO WIND). IT IS ACCEPTABLE TO ADD SHEATHING IN THESE AREAS AND SHEATHING TO BE 15/32" EXTERIOR GRADE PLYWOOD OR 1/16" O.S.B. BOARD. ATTACH PLYWOOD OR O.S.B. BOARD TO BOTTOM CHORDS OF ROOF TRUSSES WITH 10d NAILS AT 4" O.C. AT EDGES AND 6" O.C. AT INTERMEDIATE SUPPORTS. IT IS ACCEPTABLE TO COVER PLYWOOD WITH SOLID VINYL SOFFIT FL-16503.2 ATTACH SOLID VINYL SOFFIT TO PLYWOOD OR O.S.B. BOARD WITH 16 GA X 1/16" WIDTH CROWN STAPLE 5/8" MIN LENGTH @ 12" O.C. SOLID VINYL SOFFIT MEETS REQUIREMENTS OF THE 8TH EDITION OF THE 2023 F.R.B.C.

INTERIOR DOOR SCHEDULE						
ID	QTY.	ROOM	SIZE	MANUF.	DESIGNATION	NOTES
1	1	GARAGE	3068			SOLID CORE
2	1	UTILITY	(2) 2668 B.F.			
3	1	MASTER BED	2668 B.F.			
4	1	KITCHEN	2068 B.F.			
5	1	MASTER BATH	3068			
6	1	MASTER BATH	2068 B.F.			
7	1	MASTER BED	3068			
8	1	HALL	2868 B.F.			LOUVER
9	1	BEDROOM#2	3068			
10	1	BEDROOM#2	(2) 2068 B.F.			
11	1	BATH#2	3068			
12	1	BATH#2	2068 B.F.			
13	1	BEDROOM#3	3068			
14	1	BEDROOM#3	(2) 2068 B.F.			
15	1	BEDROOM#4	3068			
16	1	BEDROOM#4	(2) 2068 B.F.			

PRODUCT SCHEDULE												
ROOM NAME	MARK	CALL SIZE	R.O. DOOR SIZE		DETAIL	ZONE	DESIGN PRESS (PSF)	WINDOW / DOOR PRODUCT APPROVAL DESIGNATION / ENTITY		ENCLOSED STRUCTURE		
			R.O. WINDOW SIZE (WxH)	H				J	S	INSTALLATION NOTES (LIST BELOW)	WIND-BORNE DEBRIS REGION	TYPE GLAZING / COVERING
DOOR SCHEDULE												
LIVING ROOM	D-1	3068 MTL	3'-2" X 6'-10"		PER MFR	5	26-40/34-50	REFER TO PRODUCT APPROVAL SHEETS		Y	N/A	IMPACT APPROVED WITHOUT GLAZING OR COVERING
GARAGE	D-2	9070 O.H.G.D.	9'-0" X 7'-0"		PER MFR	5	24-72/31-20	REFER TO PRODUCT APPROVAL SHEETS	3	Y	N/A	IMPACT APPROVED WITHOUT GLAZING OR COVERING
WINDOW SCHEDULE												
BEDROOM#2	A	SH-25	37 1/4" X 62 3/4"		PER MFR	4	21-66/30-00	REFER TO PRODUCT APPROVAL SHEETS	1	Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
DINING ROOM	B	SH-25	37 1/4" X 62 3/4"		PER MFR	4	21-66/30-00	REFER TO PRODUCT APPROVAL SHEETS		Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
LIVING ROOM	C	SH-25	37 1/4" X 62 3/4"		PER MFR	5	21-66/37-02	REFER TO PRODUCT APPROVAL SHEETS		Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
LIVING ROOM	D	SH-25	37 1/4" X 62 3/4"		PER MFR	5	21-66/37-02	REFER TO PRODUCT APPROVAL SHEETS		Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
LIVING ROOM	E	SH-25	37 1/4" X 62 3/4"		PER MFR	5	21-66/37-02	REFER TO PRODUCT APPROVAL SHEETS		Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
MASTER BEDROOM	F	SH-25	37 1/4" X 62 3/4"		PER MFR	4	21-66/30-00	REFER TO PRODUCT APPROVAL SHEETS	1	Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
MASTER BEDROOM	G	SH-25	37 1/4" X 62 3/4"		PER MFR	4	21-66/30-00	REFER TO PRODUCT APPROVAL SHEETS	1	Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
BEDROOM #3	H	SH-25	37 1/4" X 62 3/4"		PER MFR	5	21-66/37-02	REFER TO PRODUCT APPROVAL SHEETS	1	Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS
BEDROOM #4	I	SH-25	37 1/4" X 62 3/4"		PER MFR	5	21-66/37-02	REFER TO PRODUCT APPROVAL SHEETS	1	Y	COVERING	HURRICANE PANELS REFER TO PRODUCT APPROVAL SHEETS

*ROOF COVERING MATERIAL		
*TYPE	*MANUFACTURER	*APPROVED MODEL, STYLE, OR DESIGNATION
ASPHALT SHINGLES	REFER TO PRODUCT APPROVAL SHEETS	REFER TO PRODUCT APPROVAL SHEETS

CODE COMPLIANCE:
1. ASPHALT SHINGLES SHALL BE IN COMPLIANCE WITH THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, SEC. R405.2
2. CLAY AND CONCRETE TILES SHALL BE IN COMPLIANCE WITH THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, SEC. R405.3
3. METAL ROOFING SHALL BE IN COMPLIANCE WITH THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, SEC. R405.10

*IMPACT RESISTANT COVERING MATERIAL		
*TYPE	*MANUFACTURER	*APPROVED MODEL, STYLE, OR DESIGNATION
HURRICANE PANELS	REFER TO PRODUCT APPROVAL SHEETS	REFER TO PRODUCT APPROVAL SHEETS

INSTALLATION NOTES:
1. MEANS OF EGRESS
2. TEMPERED WINDOW
3. O.H. GARAGE DOOR

*LEGEND:
Dx = DOOR DESIGNATION
Slx = SKYLITE DESIGNATION
Wx = WINDOW DESIGNATION

*SIZE DESIGNATIONS
W = WIDTH
H = HEIGHT

BUILDER TO VERIFY ALL ROUGH OPENINGS FOR ALL DOORS, SLIDING GLASS DOORS, AND WINDOWS PRIOR TO START OF CONSTRUCTION. BUILDER TO SUPPLY PRODUCT APPROVAL

WINDOWS SHGC = 0.24
REFER TO ATTACHED ENERGY CALCULATIONS AND ATTACHED INFORMATION FROM WINDOW AND DOOR COMPANY.

HICKS DRAFTING & DESIGN
4216 5TH STREET W
LEHIGH ACRES FL 33971
CELL: (239) 462-2734
E-MAIL: DHICKS922@AOL.COM

FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 110 1/2" CANT

BUILDER: HABITAT FOR HUMANITY
4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING

NEW RESIDENCE FOR:
LOT: / BLOCK- / UNIT- / RANGE-
SECTION: / TOWNSHIP- / ADDRESS:
ADDRESS:

DRAWN BY:
DAVID HICKS


DATE: 01-08-2021

SCALE: 1/4" = 1'0"


JOB#: 2024-007

SHEET
4 OF 6 SHEET

03-20-2024 REVISION



NOTED FLOOR PLAN



ROOF SHEATHING LAYOUT FOR HIP ROOFS

ONE WINDOW IN EACH BEDROOM SHALL PROVIDE 5.7 SQ. FT. OF EGRESS AREA MINIMUM CLEAR OPENING 20" W. AND 24" H.

MINIMUM 24" CLEAR OPENING IS REQUIRED FOR ACCESS TO ONE TOILET ROOM PER FLORIDA HANDICAP ACCESSIBILITY REQUIREMENTS.

ALL SMOKE DETECTOR CARBON MONOXIDE ALARM COMBOS TO BE INTERCONNECTED 110 VOLTS A.C.

LIGHTS IN CLOSETS TO COMPLY WITH SECT. 410-8 NEG.


PROVIDE GFI PER NEG 210-8

WATER CONSERVATION FIXTURES REQUIRED ORD#42-36

SECTION R306 ROOF VENTILATION
 R306.1 Ventilation required.
 Enclosed attics and enclosed rafter spaces formed where ceilings are applied directly to the underside of roof rafters shall have cross ventilation for each separate space by ventilating openings protected against the entrance of rain or snow. Ventilating openings shall have a least dimension of 1/16 inch (1.6 mm) minimum and 1/4 inch (6.4 mm) maximum. Ventilating openings having a least dimension larger than 1/4 inch (6.4 mm) shall be provided with corrosion-resistant wire cloth screening, hardware cloth, perforated vinyl or similar material with openings having a least dimension of 1/16 inch (1.6 mm) minimum and 1/4 inch (6.4 mm) maximum. Openings in roof framing members shall conform to the requirements of Section R302.1. Required ventilation openings shall open directly to the outside air and shall be protected to prevent the entry of birds, rodents, snakes and other similar creatures.
 R306.2 Minimum vent area.
 The minimum net free ventilating area shall be 1/150 of the area of the vented space.
 Exception: The minimum net free ventilation area shall be 1/300 of the vented space, provided that not less than 40 percent and not more than 50 percent of the required ventilating area is provided by ventilators located in the upper portion of the attic or rafter space. Upper ventilators shall be located not more than 3 feet (914 mm) below the ridge or highest point of the space, measured vertically. The balance of the required ventilation provided shall be located in the bottom one-third of the attic space. Where the location of wall or roof framing members conflicts with the installation of upper ventilators, installation more than 3 feet (914 mm) below the ridge or highest point of the space shall be permitted.
 R306.3 Vent and insulation clearance.
 Where eave or cornice vents are installed, blocking, bridging and insulation shall not block the free flow of air. Not less than a 1-inch (25 mm) space shall be provided between the insulation and the roof sheathing and at the location of the vent.
 R306.4 Installation and weather protection.
 Ventilators shall be installed in accordance with manufacturer's instructions. Installation of ventilators in roof systems shall be in accordance with the requirements of Section R303. Installation of ventilators in wall systems shall be in accordance with the requirements of Section R103.1.
 R306.5 Unvented attic and unvented enclosed rafter assemblies.
 Unvented attics and unvented enclosed roof framing assemblies created by ceilings that are applied directly to the underside of the roof framing members and structural roof sheathing applied directly to the top of the roof framing members/rafters, shall be permitted where all the following conditions are met:
 1. The unvented attic space is completely within the building thermal envelope.
 2. No interior Class I vapor retarders are installed on the ceiling side (attic floor) of the unvented attic assembly or on the ceiling side of the unvented enclosed roof framing assembly.
 3. Where wood shingles or shakes are used, a minimum 1/4-inch (6.4 mm) vented airspace separates the shingles or shakes and the roofing underlayment above the structural sheathing.
 4. In Climate Zones 5, 6, 7 and 8, any air-impermeable insulation shall be a Class II vapor retarder, or shall have a Class II vapor retarder coating or covering in direct contact with the underside of the insulation.
 5. Insulation shall comply with Item 5.3 and Item 5.1. As an alternative, where air-permeable insulation is located on top of the attic floor or on top of the attic ceiling, insulation shall comply with Item 5.3 and Item 5.2.
 5.1.1. Item 5.1, 5.1.2, 5.1.3 or 5.1.4 shall be met, depending on the air permeability of the insulation directly under the structural roof sheathing.
 5.1.1.1. Where only air-impermeable insulation is provided, it shall be applied in direct contact with the underside of the structural roof sheathing.
 5.1.2. Where air-permeable insulation is provided inside the building thermal envelope, it shall be installed in accordance with Section 5.1.1. In addition to the air-permeable insulation installed directly below the structural sheathing, rigid board or sheet insulation shall be installed directly above the structural roof sheathing in accordance with the R-values in Table R306.5 for condensation control.
 5.1.3. Where both air-impermeable and air-permeable insulation are provided, the air-impermeable insulation shall be applied in direct contact with the underside of the structural roof sheathing in accordance with Item 5.1.1 and shall be in accordance with the R-values in Table R306.5 for condensation control. The air-permeable insulation shall be installed directly under the air-impermeable insulation.
 5.1.4. Alternatively, sufficient rigid board or sheet insulation shall be installed directly above the structural roof sheathing to maintain the monthly average temperature of the underside of the structural roof sheathing above 45°F (7°C). For calculation purposes, an interior air temperature of 65°F (20°C) is assumed and the exterior air temperature is assumed to be the monthly average outside air temperature of the three coldest months.
 5.2. In Climate Zones 1, 2 and 3, air-permeable insulation installed in unvented attics on the top of the attic floor or on top of the ceiling shall meet the following requirements:
 5.2.1. An approved vapor diffusion port shall be installed not more than 12 inches (305 mm) from the highest point of the roof, measured vertically from the highest point of the roof to the lower edge of the port.
 5.2.2. The port area shall be greater than or equal to 1:600 of the ceiling area. Where there are multiple ports in the attic, the sum of the port areas shall be greater than or equal to the area requirement.
 5.2.3. The vapor-permeable membrane in the vapor diffusion port shall have a vapor permeance rating of greater than or equal to 20 perms when tested in accordance with Procedure A of ASTM E96.
 5.2.4. The vapor diffusion port shall serve as an air barrier between the attic and the exterior of the building.
 5.2.5. The vapor diffusion port shall protect the attic against the entrance of rain and snow.
 5.3. Where preformed insulation board is used as the air-impermeable insulation layer, it shall be sealed at the perimeter of each individual sheet interior surface to form a continuous layer.

THE ROOF VENTILATION MUST MEET ALL REQUIREMENTS OF SECTION R306 ROOF VENTILATION SHOWN ABOVE.
 R306.2 MINIMUM AREA CALCULATIONS:
 THE TOTAL NET FREE VENTILATING AREA SHALL BE NOT LESS THAN 1 TO 300 OF THE AREA OF THE SPACE VENTILATED.
 1172 SQ FT TOTAL ATTIC AREA TO BE VENTILATED
 1172 SQ FT DIVIDED BY 300 SQ FT = 3.91 SQ FT TOTAL VENTILATION REQUIRED.
 CONVERT TO SQ IN: 3.91 SQ FT X 144 = 563.76 SQ IN
 563.76 SQ IN DIVIDED BY 2 = 281.88 SQ IN AT SOFFITS AND 281.88 SQ IN AT RIDGE VENTS OR OFF RIDGE VENTS SEPARATE OR COMBINED.
 (GOBRA RIDGE VENT # FL-426T R2) PROVIDES 18 SQ IN PER LINEAL FT OF NET FREE VENTILATING AREA.
 (TAMCO 4" ROUND OFF RIDGE VENT FL-16118-R2) PROVIDES 138 SQ IN PER OFF RIDGE VENT.
 412.28 SQ IN DIVIDED BY 18 SQ IN PER FT OF GOBRA RIDGE VENT # 3 = 22.92 NET FREE LINEAL FT REQUIRED (26" RIDGE VENT)
 TOTAL OF VENTED SOFFIT REQUIRED = 425.28 SQ IN
 148.22 SQ IN TOTAL SUPPLIED THAT MEETS THE REQUIREMENTS FOR SOFFIT VENTILATIONS. FL-16503.2 VINYL SOFFIT 12" TRIPLE 4 FULL O VENT EGO (NO. 0694)


*NOTE: ALL BRANCH CIRCUITS THAT SUPPLY 125-250 VOLT, SINGLE PHASE, 15 AND 20 AMPERE RECEPTACLE OUTLETS SHALL BE INSTALLED IN ALL ROOMS (INCLUDING BEDROOMS) EXCEPT THE BATHROOMS, AND UTILITY ROOM IN A DWELLING UNIT AND SHALL BE PROTECTED BY AN ARC-FAULT CIRCUIT INTERRUPTER(S). KITCHEN, BATHROOMS, UTILITY ROOM, AND WET AREA'S SHALL BE PROTECTED BY G.F.C.I. OUTLETS.




ELECTRICAL PLAN

ELECTRICAL LEGEND

SYMBOL	DESCRIPTION
	Audio Video: Control Panel, Switch
	DENOTES WALL OUTLET TAMPER RESISTANT
	DENOTES GFCI WALL OUTLET
	DENOTES WATER PROOF WALL OUTLET
	DENOTES 220 VOLT WALL OUTLET
	DENOTES FLOOR OUTLET
	DENOTES COVERED FLOOR OUTLET
	DENOTES T.V. OUTLET
	DENOTES DOOR BELL
	DENOTES PHONE OUTLET
	DENOTES THERMOSTAT
	DENOTES 200 AMP SERVICE BOX
	DENOTES WALL SWITCH
	DENOTES 3 WAY SWITCH
	DENOTES 4 WAY SWITCH
	DENOTES 5 WAY SWITCH
	DENOTES DIMMER SWITCH
	DENOTES WATER PROOF SWITCH
	DENOTES CEILING OR WALL FIXTURE
	DENOTES RECESS FIXTURE
	DENOTES EXHAUST FAN
	DENOTES SMOKE DETECTOR
	DENOTES SMOKE DETECTOR CARBON MONOXIDE ALARM COMBO
	DENOTES JUNCTION BOX & COVER FOR FUTURE FAN
	DENOTES JUNCTION BOX W/COVER
	DENOTES ZENFLEX LOW VOLTAGE LIGHTING SYSTEM
	Wall Jacks: CAT5, CAT5 + TV, TV/Cable
	Intercom
	Speakers: Ceiling Mounted, Wall Mounted
	240V Receptacle
	Thermostat
	Wall Mounted Light Fixtures: Flush Mounted, Wall Sconce
	Chandelier Light Fixture




TYPICAL WINDOW INSTALLATION DETAIL



- "A" SIMPSON MAS CONNECTOR WITH (6) 10d X 1 1/2" NAILS @ 2'-0" O.C. (PLATE TO SLAB) OR 1/2" J-BOLT (7" MINIMUM EMBEDMENT) AND 2" X 2" X 1/8" PLATE WASHER @ 16" O.C. OR 1/2" X 6" TITEN HD SCREWS @ 16" O.C.
- "B" SIMPSON HD-3B SHEAR WALL HOLDOWN W/(2) 5/8" DIA. BOLTS PER STUD AND (1) 5/8" X 6" LONG EXPANSION BOLT
- "C" SIMPSON H-2.5A OR H-3 OR EQUAL (STUD TO PLATE)
- "D" SIMPSON H10A WITH (18) 10d X 1 1/2" NAILS OR EQUAL (TRUSS TO PLATE)
- "E" SIMPSON LSTA-18 WITH (14) 10d NAILS

FRAMING DETAIL (TYP.)



ROOF SHEATHING DETAIL

GENERAL NOTES
 1. CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO START OF CONSTRUCTION. DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.
 2. MASONRY CONTRACTOR TO VERIFY MASONRY OPENING DIMENSIONS FOR ALL WINDOWS, SLIDING GLASS DOORS, & ENTRY DOORS AS SHOWN ON THESE PLANS WITH THE DOOR AND WINDOW MANUFACTURER PRIOR TO CONSTRUCTION.
 3. IT IS THE CONTRACTORS RESPONSIBILITY TO CHECK THESE PLANS FOR DIMENSIONAL ERRORS AND OMISSIONS PRIOR TO CONSTRUCTION. IF ANY ERRORS OR OMISSIONS EXIST IN THE DRAWINGS OR SPECIFICATIONS, THE CONTRACTOR SHALL NOTIFY HICKS DRAFTING & DESIGN IN WRITING WITHIN 10 DAYS OF RECEIPT OF PLANS AND PRIOR TO ANY CONSTRUCTION OR CONTRACTOR ASSUMES ALL THE RESPONSIBILITY FOR THE RESULTS AND ALL THE COSTS OF RECTIFYING THE SAME.
 4. HICKS DRAFTING & DESIGN DOES NOT ASSUME ANY RESPONSIBILITY FOR SUPERVISION OF CONSTRUCTION. CONTRACTOR TO ADHERE STRICTLY TO THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, CHAPTER 3, AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE, TOGETHER WITH LOCAL AMENDMENTS, AND ALL OTHER APPLICABLE STATE, COUNTY, AND LOCAL STATUTES, ORDINANCES, REGULATIONS, AND RULES.

NOTE: MASTER PLANS FEMA/FLOOD ZONES CONSTRUCTION NEW CONSTRUCTION OF ANY RESIDENTIAL STRUCTURE SHALL HAVE THE LOWEST FLOOR OR CONCRETE SLAB, INCLUDING GARAGE OR BASEMENT AND A/C W/H AND ALL EQUIPMENT, ELEVATED TO FINISH FLOOR ELEV. OR ABOVE THE BASE FLOOD ELEVATION PLUS 1 FOOT. THIS SHALL APPLY TO HOUSES OR MANUFACTURED HOMES THAT ARE TO BE PLACED OR SUBSTANTIALLY IMPROVED ON SITES IN A NEW MANUFACTURED HOME PARK OR SUBDIVISION LCD CHAPTER 6, ARTICLE IV FLOOD HAZARD REDUCTION.

THIS RESIDENCE MAY NOT BE BUILT WITHIN 60" OF ANOTHER STRUCTURE OR 90" FROM ANY PROPERTY LINE PER SECTION R302.1(1) (INCLUDING OVERHANGS)

Quattrone & Associates, Inc.
 Engineers, Planners, & Development Consultants
 4401 Vermont Shorebank Blvd., Fort Myers, FL 33916 (239) 936-9222 QAM@ca.com
 Certificate of Authorization Number 9463
 AL QUATTRONE P.E. # 52141

REVISIONS:
 02-23-2022
 03-20-2024

HICKS DRAFTING & DESIGN
 4216 5TH STREET W
 LEHIGH ACRES FL 33971
 CELL: (239) 462-2734
 E-MAIL: DHICKS922@AOL.COM

BUILDER: HABITAT FOR HUMANITY
 4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING
 NEW RESIDENCE FOR: / UNIT- / RANGE-
 LOT- / BLOCK- / TOWNSHIP-
 SECTION- / STRAP# / ADDRESS:
 ADDRESS:

DRAWN BY:
 DAVID HICKS
DATE: 01-08-2021
SCALE: 1/4"=10"
JOB#: 2024-007
SHEET
 5 OF 6 SHEET

FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 110 1/2" CANT

TABLE R503.2.1
ROOF SHEATHING ATTACHMENTS, b

RAFTER/TRUSS SPACING 24 IN. O.C.	WIND SPEED																	
	115 mph			120 mph			130 mph			140 mph			150 mph			160 mph		
	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F
Rafter/Truss Sg = 0.42	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Rafter/Truss Sg = 0.44	6	12	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Rafter/Truss Sg = 0.42	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Rafter/Truss Sg = 0.44	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Rafter/Truss Sg = 0.42	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Rafter/Truss Sg = 0.44	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6

TABLE R503.2.2
MINIMUM ROOF SHEATHING THICKNESS


RAFTER/TRUSS SPACING 24 IN. O.C.	WIND SPEED																	
	115 mph			120 mph			130 mph			140 mph			150 mph			160 mph		
	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure B	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure C	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure D	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure E	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2

R503.2.2 Allowable spans. The minimum thickness and span rating for wood structural panel roof sheathing shall not exceed the values set forth in Table R503.2.2.

TABLE R503.2.2
MINIMUM ROOF SHEATHING THICKNESS


RAFTER/TRUSS SPACING 24 IN. O.C.	WIND SPEED																	
	115 mph			120 mph			130 mph			140 mph			150 mph			160 mph		
	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F	E	F	F
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure B	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure C	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure D	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2
Minimum Sheathing Thickness, inches (Panel Span Rating) Exposure E	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2	1/2

ASPHALT SHINGLES R905.2 SHALL HAVE SEAL STRIPS OR BE INTERLOCKING AND COMPLY WITH ASTM D-225 OR ASTM D-3462 AND SHINGLES NEED TO BE CLASSIFIED AS (H) OR (F) PER TABLE 1507.2 & TABLE R405.2.6.1.




RIGHT SIDE ELEVATION

ASPHALT SHINGLES R905.2 SHALL HAVE SEAL STRIPS OR BE INTERLOCKING AND COMPLY WITH ASTM D-225 OR ASTM D-3462 AND SHINGLES NEED TO BE CLASSIFIED AS (H) OR (F) PER TABLE 1507.2 & TABLE R405.2.6.1.




LEFT SIDE ELEVATION

HORIZONTAL VINYL SIDING (TYPICAL AT ALL ELEVATIONS)
TOP OF ALL WINDOWS AT 6'-8" A.F.F. U.N.O.



BACK ELEVATION

HORIZONTAL VINYL SIDING (TYPICAL AT ALL ELEVATIONS)
TOP OF ALL WINDOWS AND DOORS ARE SET AT 6'-8" ABOVE FINISH FLOOR



FRONT ELEVATION

TOP OF GARAGE DOOR AT 7'-0" TALL U.N.O.
TOP OF ALL WINDOWS AND DOORS ARE SET AT 6'-8" ABOVE FINISH FLOOR

EXTERIOR ELEVATIONS

DESIGN PARAMETERS:

APPLICABLE CODES:
 BUILDING CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023
 MECHANICAL CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, MECHANICAL 2023
 PLUMBING CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, PLUMBING 2023
 ELECTRICAL CODE = NEC 2020
 FLORIDA FIRE PREVENTION CODE = 8TH EDITION
 LIFE SAFETY CODE = NFPA 101 8TH EDITION

ACCESSIBILITY CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023
 ENERGY CODE = (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023

METHOD OF DESIGN:
 DESIGNED PURSUANT TO (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, BUILDING 2023, CHAPTER 3 AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE

BASIC WIND SPEED:
 110 MPH (ULTIMATE DESIGN) = 132.0 MPH (NOMINAL DESIGN)
 160 MPH (ULTIMATE DESIGN) = 124 MPH (NOMINAL DESIGN)
 150 MPH (ULTIMATE DESIGN) = 116 MPH (NOMINAL DESIGN)

IMPORTANCE FACTOR/COMPONENTS AND CLADDING:
 0.11 (RISK CATEGORY I)
 0.15 (RISK CATEGORY II)
 0.15 (RISK CATEGORY III)
 1.15 (RISK CATEGORY IV)

BUILDING OCCUPANCY CLASSIFICATION:
 GROUP A - ASSEMBLY
 GROUP B - BUSINESS
 GROUP D - DAY CARE CENTER
 GROUP E - EDUCATIONAL
 GROUP F - FACTORY INDUSTRIAL
 GROUP H - HAZARDOUS
 GROUP I - INSTITUTIONAL
 GROUP M - MERCANTILE
 GROUP R - RESIDENTIAL
 GROUP S - STORAGE

TORNADO BASIC WIND SPEED:
 RISK CATEGORY II = N/A
 170 MPH (NORMAL DESIGN F3-SECOND GUST)
 160 MPH (NORMAL DESIGN F3-SECOND GUST)
 150 MPH (NORMAL DESIGN F3-SECOND GUST)

RAIN FALL INFORMATION:
 N/A SLOPED ROOF GREATER THAN 2/12
 RAINFALL DATA FROM FBC PLUMBING 2023 FIGURE 1106.1 IN./HR.
 ROOF AREA IN SF.

BUILDING CONSTRUCTION TYPE:
 TYPE I
 TYPE II
 TYPE III
 TYPE IV
 TYPE V

EXPOSURE CATEGORY:
 A
 B
 C
 D

WINDBORNE DEBRIS REGION:
 NO
 YES

INTERNAL PRESSURE COEFFICIENTS:
 0.00 (OPEN)
 0.18, -0.18 (ENCLOSED)
 +0.55, -0.55 (PARTIALLY ENCLOSED)

CLASSIFICATION OF WORK:
 ALTERATION
 LEVEL 1
 LEVEL 2
 LEVEL 3
 NEW CONSTRUCTION
 CHANGE OF OCCUPANCY
 ADDITION / REMODEL
 HISTORIC BUILDING

DESIGN LOAD BEARING VALUE OF SOIL 2000 PSF

GENERAL NOTES

1. CONTRACTOR TO VERIFY ALL DIMENSIONS PRIOR TO START OF CONSTRUCTION. DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.

2. MASONRY CONTRACTOR TO VERIFY MASONRY OPENING DIMENSIONS FOR ALL WINDOWS, SLIDING GLASS DOORS, & ENTRY DOORS AS SHOWN ON THESE PLANS WITH THE DOOR AND WINDOW MANUFACTURER PRIOR TO CONSTRUCTION.

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CHECK THESE PLANS FOR DIMENSIONAL ERRORS, AND/OR OMISSIONS PRIOR TO CONSTRUCTION. IF ANY ERRORS OR OMISSIONS EXIST IN THE DRAWINGS OR SPECIFICATIONS, THE CONTRACTOR SHALL NOTIFY HICKS DRAFTING & DESIGN IN WRITING WITHIN 10 DAYS OF RECEIPT OF PLANS AND PRIOR TO ANY CONSTRUCTION OR CONTRACTOR ASSUMES ALL THE RESPONSIBILITY FOR THE RESULTS AND ALL THE COSTS OF RECTIFYING THE SAME.

4. HICKS DRAFTING & DESIGN DOES NOT ASSUME ANY RESPONSIBILITY FOR SUPERVISION OF CONSTRUCTION. CONTRACTOR TO ADHERE STRICTLY TO THE (8TH EDITION) OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, CHAPTER 3, AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE, TOGETHER WITH LOCAL AMENDMENTS, AND ALL OTHER APPLICABLE STATE, COUNTY, AND LOCAL STATUTES, ORDINANCES, REGULATIONS, AND RULES.

NOTE: MASTER PLANS FEMA FLOOD ZONES CONSTRUCTION NEW CONSTRUCTION OF ANY RESIDENTIAL STRUCTURE SHALL HAVE THE LOWEST FLOOR OR CONCRETE SLAB, INCLUDING GARAGE OR BASEMENT AND ACQUIN AND ALL EQUIPMENT, ELEVATED TO FINISH FLOOR ELEV. OR ABOVE THE BASE FLOOD ELEVATION PLUS 1 FOOT. THIS SHALL APPLY TO HOUSES OR MANUFACTURED HOMES THAT ARE TO BE PLACED OR SUBSTANTIALLY IMPROVED ON SITES IN A NEW MANUFACTURED HOME PARK OR SUBDIVISION LDC CHAPTER 6 ARTICLE IV FLOOD HAZARD REDUCTION.

THIS RESIDENCE MAY NOT BE BUILT WITHIN 60' OF ANOTHER STRUCTURE OR 90' FROM ANY PROPERTY LINE PER SECTION R302.1(1) (INCLUDING OVERHANGS)

Quattrone & Associates, Inc.
 Engineers, Planners, & Development Consultants
 4400 Vermont Shorebank Blvd., Fort Myers, FL 33916 (239) 936-9222 Q&Ainc.com
 Certificate of Authorization Number 9463
 AL-QUATTRONE P.E. # 52141

CONFORMANCE STATEMENT
 THESE PLANS HAVE BEEN DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF FLORIDA UNDER THE FLORIDA BUILDING CODE (8TH EDITION) OF THE GENERAL AND SECTION 1609 OF THE (8TH EDITION) OF THE 2023 FLORIDA BUILDING CODE.

REVISIONS:

02-23-2022
03-20-2024

BUILDING OVERHANG TO BE 5 FEET FROM PROPERTY LINE UNLESS RATED OR FIRE SPRINKLERED TABLE R302.1(1)

DECK BOARDS & STAIR TREADS REQUIRED TO HAVE LABEL R507

ONE LAYER OF WATER RESISTIVE BARRIER BEHIND EXTERIOR SIDING WALL COVERING RT03.2

TWO LAYERS OF WATER RESISTIVE BARRIER BEHIND EXTERIOR WALLS WITH WIRE LATH & CEMENTITIOUS FINISH COVERING RT03.3

PAN FLASHING UNDER WINDOWS AND DOORS ON FRAME CONSTRUCTION. REFER TO NOTES RT03.4 ON SHEET 3 OF 6


WINDOWS MUST HAVE COMPLIANT SHGC VALUES. REFER TO EXTERIOR OPENING CHART AND ATTACHED ENERGY CALCULATIONS AND WINDOW AND DOOR SPEC SHEETS FROM MANUFACTURERS.

WATER HEATERS AND STORAGE TANKS SHALL BE EQUIP WITH PRESSURE RELEASE AND TEMPERATURE VALVES OR A COMBINATION THEREOF 504 WATER TANK SAFETY DEVICES.

THE MAXIMUM DISTANCE BETWEEN A HOT WATER SUPPLY SOURCE AND ALL FIXTURES SERVED BY THE SUPPLY SOURCE HAS BEEN REDUCED FROM 100 FT TO 50 FT. HOT OR TEMPERED WATER SUPPLY TO FIXTURES

PLAN SCHEDULE

SHEET #	DESCRIPTION
1 OF 6	EXTERIOR ELEVATIONS, ROOF PLAN, SECTIONS
2 OF 6	FOUNDATION PLAN, WALL SECTION, AND SECTIONS
3 OF 6	DIMENSIONAL FLOOR PLAN AND SECTIONS
4 OF 6	NOTED FLOOR PLAN, SCHEDULES, AND SECTIONS
5 OF 6	ELECTRICAL PLAN, ELECTRICAL SCHEDULE AND SECTIONS
6 OF 6	ENGINEERING NOTES AND SECTIONS
1A OF 6	ALTERNATE EXTERIOR ELEVATIONS, ROOF PLAN, SECTIONS
SH-1 OF SH-2	SHOP DRAWINGS
SH-1 OF SH-2	SHOP DRAWINGS



ROOF PLANE PLAN

4/12 PITCH ROOF
 2X4 TOP CHORD
 10 1/2" CANT PLUMB OVERHANG
 TRUSSES BEARING AT 8'0" ELEV. A.F.F. TYPICAL
 160 MPH WIND LOAD
 40 LBS LOADING/ASPHALT SHINGLES

(A) ANCHOR GIRDER TRUSS WITH (1) SIMPSON HTS-20 (TYPICAL)

(B) ANCHOR GIRDER TRUSS WITH (2) SIMPSON HTS-20 (TYPICAL)

NOTE: ATTACH 6X6 FT. POST BOTTOM TO CONCRETE WITH ABU-66 OR ALTERNATE ANCHOR AND AT TOP TO BEARING BEAMS WITH CG COLUMN CAP OR ALTERNATE ST6224 STRAP TYPICAL.

(2) 1 3/4" X 11 7/8" MICROLAM IN SIMPSON ST6226 IN (40) 16D NAILS AT WALL END. 3 NAILS STUDS BELOW EACH END.

RL-1 36" HIGH DEC VINYL RAILING NON GUARDRAIL. OPENING WILL RESIST 4" SPHERE. ATTACH PER MANUFACTURERS SPECIFICATIONS.

MASTER PLAN
 I AL QUATTRONE APPROVE OF REPETITIVE USE OF PLANS FOR PERMITTING
 FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 10 1/2" CANT

HICKS DRAFTING & DESIGN
 4216 5TH STREET W
 LEHIGH ACRES FL 33971
 CELL: (239) 462-2734
 E-MAIL: DHICKS922@AOL.COM

BUILDER: HABITAT FOR HUMANITY
 4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING

NEW RESIDENCE FOR:
 LOT: / BLOCK- / UNIT-
 SECTION: / TOWNSHIP- / RANGE-
 STRAP#:
 ADDRESS:

DRAWN BY:
DAVID HICKS

DATE: 01-08-2021

SCALE: 1/4" = 1'0"

JOB#: 2024-007

SHEET
1A OF 6 SHEET

03-20-2024 REVISION


03-20-2024

FOXTAIL 2 MODEL WALL SCHEDULE			
WALL#	LENGTH	EXTERIOR OR INTERIOR	NOTES
1	8'-0"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
2	12'-0"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
3	12'-0"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
4	10'-11"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
5	15'-3"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
6	1'8 1/2"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
7	14'-4 1/2"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
8	11'-4"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
9	12'-0"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
10	12'-0"	EXTERIOR/ INTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
11	13'-4"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
12	9'-3"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
13	14'-4 1/2"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
14	4'-3"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
15	8'-3-1/2"	EXTERIOR	2 X 6 SYP #2 WALL NO PLYWOOD (PLUMBING)
16A	4'-5"	EXTERIOR	2 X 4 SYP #2 WALL NO PLYWOOD
17	11'-0"	EXTERIOR	2 X 4 SYP #2 WALL NO PLYWOOD
18	10'-8-1/2"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
19	13'-0"	EXTERIOR	2 X 4 SYP #2 WALL WITH PLYWOOD
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			

NOTE: ALL DIMENSIONS AS PER BUILDER

FOXTAIL 2 MODEL LVL BEAM SCHEDULE		
BEAM #	LENGTH	BEAM TYPE
A		
B		
C		
D		

FOXTAIL 2 MODEL 2 X 12 SYP. BEAM SCHEDULE		
BEAM #	LENGTH	BEAM TYPE
E	9'-6"	(2) 2 X 12 SYP. W/ 1/2" PLYWOOD FLITCH PLATES (GLUED & NAILED)
F	2'-6"	(2) 2 X 12 SYP. W/ 1/2" PLYWOOD FLITCH PLATES (GLUED & NAILED)
G	16'-0 1/2"	(2) 2 X 12 SYP. W/ 1/2" PLYWOOD FLITCH PLATES (GLUED & NAILED)
H	4'-6"	(2) 2 X 12 SYP. W/ 1/2" PLYWOOD FLITCH PLATES (GLUED & NAILED)



NOTE: EXTERIOR WOOD WALLS ARE 3 1/2" WIDE WITH 15/32" PLYWOOD. (4" TOTAL) UNLESS NOTED DIFFERENT..
 INTERIOR WOOD WALLS ARE 3 1/2" & 5 1/2" WIDE WOOD WALLS UNLESS NOTED DIFFERENT.

INTERIOR & EXTERIOR WALL FRAMING PLAN
 SCALE :N.T.S.

Quattrone & Associates, Inc.
 Engineers, Planners, & Development Consultants
 4100 Vermont Shorebank Blvd. Fort Myers, FL 33916 (239) 936-9322 QAMc.net
 Certificate of Authorization Number 9463
 AL-QUATTRONE P.E. # 52141

COMPLIANCE STATEMENT
 THESE PLANS HAVE BEEN DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER UNDER THE SUPERVISION OF A REGISTERED PROFESSIONAL ARCHITECT UNDER THE JURISDICTION OF THE 2023 FLORIDA RESIDENTIAL BUILDING CODE (R-30) AND THE GENERAL AND SECTION 1609 OF THE (6TH EDITION) OF THE 2023 FLORIDA BUILDING CODE.

REVISIONS:
02-23-2022
03-20-2024

HICKS DRAFTING & DESIGN
 4216 5TH STREET W
 LEHIGH ACRES FL 33971
 CELL: (239) 462-2734
 E-MAIL: DHICKS922@AOL.COM

FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 10 1/2" CANT

BUILDER: HABITAT FOR HUMANITY
 4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING

NEW RESIDENCE FOR:
 LOT: /BLOCK- /UNIT- /RANGE-
 SECTION: /TOWNSHIP-
 STRAP#
 ADDRESS:

03-20-2024 REVISION


DRAWN BY:
 DAVID HICKS

DATE: 01-08-2021

SCALE: 1/4"=1'0"

JOB#: 2024-007

SHEET
 SH-1 SH-2
 OF SHEET



CENTER LINE OF WINDOWS LOCATION PLAN
SCALE :N.T.S.

NOTE: EXTERIOR WOOD WALLS ARE 3 1/2" WIDE WITH 1/2" PLYWOOD.
(4" TOTAL) UNLESS NOTED DIFFERENT..
INTERIOR WOOD WALLS ARE 3 1/2" & 5 1/2" WIDE WOOD WALLS
UNLESS NOTED DIFFERENT.

Quattrone & Associates, Inc.
Engineers, Planners, & Development Consultants
4100 Vermont Shorebank Blvd. Fort Myers, FL 33916 (239) 936-6222 QAI@cs.net
AL QUATTRONE P.E. # 52141

COMPLIANCE STATEMENT
THESE PLANS HAVE BEEN DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER AND CONFORM WITH THE 2023 FLORIDA RESIDENTIAL BUILDING CODE, CHAPTER 630, GENERAL AND SECTION 1609 OF THE (6TH EDITION) OF THE 2023 FLORIDA BUILDING CODE.

REVISIONS:
02-23-2022
03-20-2024

HICKS DRAFTING & DESIGN
4216 5TH STREET W
LEHIGH ACRES FL 33971
CELL: (239) 462-2734
E-MAIL: DHICKS922@AOL.COM

FOXTAIL 2 MODEL / LEFT HAND GARAGE / MONO FOOTER / 2023 CODE / 10 1/2" CANT
BUILDER: HABITAT FOR HUMANITY
4 BEDROOM 2 BATH HOME / 160 MPH WIND LOADING
NEW RESIDENCE FOR:
LOT: / BLOCK- / UNIT-
SECTION: / TOWNSHIP. / RANGE-
STRAP#
ADDRESS:

03-20-2024 REVISION
DRAWN BY:
DAVID HICKS
DATE: 01-08-2021
SCALE: 1/4"=1'0"
JOB#: 2024-007
SHEET
SH-2 OF SH-2 OF SHEET